

CSI Line Number	Description	Unit	2008 Book	1st Qtr.	2nd Qtr.	3rd Qtr.	Current % Change	Total Incl. New Cost \$	O&P % Change
			Material Cost \$	New Cost \$	New Cost \$	New Cost \$			
Division 3 — CONCRETE									
03 05 13.30 0300	Cement, portland, plain, trucked in bulk	Cwt.	6.90	6.90				7.59	
0400	Cement, portland, high early strength, T.L. lots, 94 lb bags	Bag	10.70	10.70				11.77	
03 21 10.60 0100	Reinforcing in place, A615 Gr 60, beams and girders, #3 to #7	Ton	935	955			2.14	2,450.50	.91
03 22 05.50 0100	Welded wire fabric, sheets, 6 x 6 - W1.4 x W1.4 (10 x 10), 21 lb/CSF	C.S.F.	13.25	13.50			1.89	47.35	.57
03 31 05.35 0150	Concrete, ready mix, regular weight, 3000 psi	C.Y.	100	100				110	
0400	Concrete, ready mix, regular weight, 5000 psi	C.Y.	109	109				119.90	
03 41 13.50 0100	Structural precast, slabs, prestressed, roof & floor, grouted, 8" thk	S.F.	7.20	7.20				10.22	
03 41 33.60 1350	Structural precast, dbl tees, floor, std weight, 18" dp x 8" wide, 30' span	Ea.	1,775	1,775				2,320.50	
03 45 13.50 0750	Wall panels, precast, insulated panel, 20' x 10', 6" thick, smooth gray	S.F.	24	24				31.66	
Division 4 — MASONRY									
04 05 13.10 0100	Cement, masonry, 70 lb. bag, T.L. lots	Bag	9.05	9.05				9.96	
20 0020	Lime, masons, hydrated, 50 lb. bag, T.L. lots	Bag	7.55	7.55				8.31	
95 0020	Sand, for mortar, screened and washed	Ton	15.15	15.15				16.67	
04 21 13.45 0350	Face brick, C216, standard, T.L. lots, 4" x 2-2/3" x 8", max	M	775	775				852.50	
04 22 10.34 4200	CMU partition, no scaf/reinf, normal wt, hollow, 8" x 8" x 16"	S.F.	2.07	2.07				8.08	
04 43 10.45 0150	Granite, veneer, polished face, 3/4" to 1-1/2" thk, gray/lt gray, low price	S.F.	24.50	24.50				46.30	
0220	Granite, veneer, polished face, 2" thk, red/black, high price	S.F.	38.50	38.50				61.70	
Division 5 — METALS									
05 05 23.90 0660	Weld rod, steel, type 7018 Low Hydrogen, 1/8" dia, 500# to 2,000#	Lb.	1.79	1.79				1.97	
05 12 23.45 0100	Lintels, plain steel angles, 500 to 1000 lb.	Lb.	.83	.83				1.65	
77 0700	Structural steel projects, offices, hosp, etc, bolted, 1 to 2 stories	Ton	2,200	2,200				3,176	
05 14 23.05 0100	Aluminum, structural shapes, 1" to 10" members, over 5 tons	Lb.	2.45	2.50			2.04	7.09	.71
05 21 19.10 0440	Open web joists, K series, horiz bridging, 30' to 50', average	Ton	1,475	1,475				2,090.50	
05 31 13.50 5900	Metal decking, non-cellular composite, galv, 3" deep, 18 gauge	S.F.	2.29	2.29				3.45	
05 31 23.50 2200	Metal decking, open, galv, 1-1/2" deep, wide rib, 22 ga, 50-500 sq.	S.F.	1.25	1.25				1.92	
05 51 13.50 0350	Stair, steel, cement fill metal pan, wall rail both sides, 3'-6" wide	Riser	315	315				396.74	
05 52 13.50 0640	Railing, pipe, steel, 3 rail, galvanized, 1-1/2" diameter	L.F.	50.50	50.50				74.96	
Division 6 — WOOD, PLASTICS & COMPOSITES									
06 11 10.30 7820	Framing, roofs, ridge board, #2 or better, 1" x 6"	M.B.F.	1,250	1,240			-0.80	4,539	-0.24
40 6020	Framing, walls, plates, untreated, 2" x 4"	M.B.F.	530	520			-1.89	2,372	-0.46
06 16 36.10 0100	Sheathing, plywood on roof, CDX, 1/2" thick	S.F.	.52	.52				1.25	
Division 7 — THERMAL & MOISTURE PROTECTION									
07 01 50.10 0012	Roof coatings, asphalt, brush grade	Gal.	7.50	7.50				8.25	
07 21 13.10 1660	Wall insul, rigid isocyanurate, foil faced, 2" thk, R14.4	S.F.	.87	.86			-1.15	1.60	-0.62
07 21 16.20 0080	Wall/ceiling insul, fbcls, kraft faced, batt/blkt, 3.5" thk, R11,15" W	S.F.	.37	.37				.76	
07 31 13.10 0150	Asphalt shingles, std strip shingles, inorganic, class A, 210-235 lb/sq	Sq.	43	42			-2.33	127.70	-0.85
07 51 13.40 0900	Felt, asphalt, #15, 4 sq per roll, no mopping	Sq.	4.10	4			-2.44	12.15	-0.90
07 53 23.20 4810	E.P.D.M., 45 mil, .28 PSF, membrane only	Sq.	34	36			5.88	39.60	5.88
07 72 33.10 0520	Roof hatches, with curb, insul, galv st, curb & al cover, 2'-6" x 3'-0"	Ea.	695	695				951.50	
Division 8 — OPENINGS									
08 12 13.13 1000	Frame, stl, knock dn, 16 ga, single, to 4-7/8" dp, 7'-0" H, 3'-0" W	Ea.	127	127				199.20	
25 0400	Frame, 10" stl chan, 15.3 #/LF, anchor/bar stop, 10'x10' door	Ea.	660	660				1,170	
08 13 13.13 1120	Door, comm, stl flush, full panel, hol core, 18 ga, 1.75" thk, 3'-0" x 7'-0"	Ea.	360	360				452	
08 14 33.20 7780	Door, wood, resi, pass, flush, birch, hol core, 1-3/8" thk x 6'-8" x 3' W	Ea.	51	51				112.10	
08 41 13.20 0200	Tube frame, window wall/store frts,alum,stock tube, mill fin,1-3/4"x4-1/2"	L.F.	10.70	10.70				21.27	
08 52 10.40 0150	Casement window, frame/scrn/ext trim, bldrs model, 2'-0"x3'-0" H, insul glass	Ea.	281	281				356.60	
08 71 20.40 0400	Lockset, std duty, cylindrical, sectional trim, keyed, sgl cyl function	Ea.	77	77				132.20	
08 81 10.10 0600	Float glass, 1/4" thick, plain, clear	S.F.	4.86	4.86				12.90	
08 81 30.10 0400	Insul glass, 1" thk, dbl glazed, 1/4" float, 30-70 SF, clear	S.F.	13.95	13.95				27.40	
Division 9 — FINISHES									
09 22 16.13 2800	Metal stud, non-load brg, galv, 20 ga., 3-5/8" W, 16" O.C.	S.F.	.52	.52				1.80	
09 29 10.30 0300	Gypsum wallboard, 1/2" thk, on walls, std, no finish	S.F.	.25	.25				.75	
09 30 13.10 5400	Ceramic tile, walls, interior, thin set, 4-1/4" x 4-1/4"	S.F.	2.22	2.22				6.53	
09 51 53.10 0600	Ceiling tile, mineral fiber, vinyl coated, 12"x12"/24", 5/8" thk	S.F.	1.65	1.65				3.40	
09 53 23.30 0050	Suspension systems for boards & tile, class A, 15/16" T bar, 2' x 4' grid	S.F.	.53	.53				1.17	
09 64 29.10 4700	Wood strip floor, oak, white or red, 25/32" x 2-1/4", # 1 common, no finish	S.F.	3.09	3.09				6.19	
09 65 13.13 1500	Cove base, rubber or vinyl, std colors, 1/8" thk, 4" high	L.F.	.65	.65				2.10	
09 65 19.10 7350	Resilient flooring, vinyl comp tile, 12" x 12", 1/8" thick, marbled/leized	S.F.	1.55	1.55				2.58	
09 68 16.10 0700	Carpet, comm grade, dir cem, nylon, level loop, 26 oz, lt to med traffic	S.Y.	24	24				32.20	

CSI Line Number	Description	Unit	2008 Book	1st Qtr.	2nd Qtr.	3rd Qtr.	Current % Change	Total Incl.	O&P %
			Material Cost \$	New Cost \$	New Cost \$	New Cost \$		New Cost \$	Change
Division 10 — SPECIALTIES									
10 21 13.16 2600	Toilet cubicle, fir mtd, headrail braced, plastic lam on part board	Ea.	555	555				768.50	
10 22 19.43 1200	Partition, demount gyp sys, moveable, 2/2.5" stl std, 9'h, 3/3.75" thk, vin clad	L.F.	56.50	56.50				81.90	
Division 11 — EQUIPMENT									
11 13 19.10 4700	Loading dock levelers, hydraulic, 10 ton capacity, 6' x 8'	Ea.	7,875	7,875				9,904.50	
11 26 13.10 1600	Combination range/refrigerator/sink, office model, 48" wide	Ea.	2,250	2,250				3,025	
Division 12 — FURNISHINGS									
12 21 16.13 1500	Blinds, vertical, 3" to 5" PVC or cloth strips, minimum	S.F.	5.20	5.20				6.75	
12 48 13.13 0500	Floor mat, link mats, including nosings, aluminum, 3/8" thick	S.F.	19.80	19.80				24.21	
Division 13 — SPECIAL CONSTRUCTION									
13 49 19.50 0910	Shielding lead, 5/8" gypsum board with 1/8" lead	S.F.	12.95	12.95				20.70	
Division 14 — CONVEYING EQUIPMENT									
14 24 23.10 2050	Elevator, hyd pass, base unit, 1500 lb, 100 fpm, 2 stop, std finishes	Ea.	33,800	33,800				50,280	
14 31 10.10 1020	Escalator, glass, 32" wide x 15' floor to floor height	Ea.	74,000	74,000				123,915	
Division 21 FIRE SUPPRESSION									
21 13 13.50 3740	Sprinkler sys, heads, std spray, brass, 135° to 286°F, 1/2" NPT, 1/2" orifice	Ea.	6.40	6.40				42.04	
Division 22 — PLUMBING									
22 11 13.23 2140	Pipe, copper, solder jts, 1/2" dia, type L tubing, cplg and 3 hrs/10' O.C.	L.F.	2.26	2.26				9.44	
44 0610	Pipe, steel, Sch 40, black, thrded, 2" dia, cplg and 3 clv type hrs/10' OC	L.F.	7.90	7.90				24.49	
74 1910	Pipe, plastic, PVC, Sch 40, 3 hrs and cplg/10' O.C., 2" dia.	L.F.	2.07	2.07				19.43	
22 13 16.20 2160	Pipe, Cl, soil, on hrs 5' O.C., lead & oakum jts 10' O.C., 4" dia.	L.F.	10.95	10.95				30.45	
22 34 36.13 6080	Water heater, comm, gas, flush jkt, std control, 120 MBH input, 110 GPH	Ea.	4,125	4,125				5,007.50	
22 41 13.40 1100	Water closet, tank, vit china, seat, fir mtd, supply w/stop, 2 piece	Ea.	183	183				392.30	
Division 23 — HEATING, VENTILATING & AIR CONDITIONING									
23 13 13.23 1100	Tank, fiberglass, undergrnd, dbl wall, 8000 gal, UL, incl manway	Ea.	17,900	17,900				20,740	
23 31 13.13 0150	Ductwork, fab rect, alum alloy 3003-H14, 2,000 to 5,000 lb., incl ftgs	Lb.	2.28	2.28				14.56	
0580	Ductwork, fab rect, galv steel, over 5000 lb, incl ftgs	Lb.	.57	.57				6.13	
23 52 23.20 3140	Boiler, gas, Cl, std controls, insul jkt, hot water, 320 MBH gross output	Ea.	3,750	3,750				6,825	
23 74 33.10 2120	Roof top A/C, curb, multizone, elec, gas, econ, 20 ton, 360 MBH	Ea.	68,000	68,000				78,850	
Division 26 — ELECTRICAL									
26 05 19.90 1250	Wire, 600 volt, type THWN-THHN, copper, stranded, #10	C.L.F.	24	21.75			-9.38	78.43	-3.05
26 05 33.05 5020	EMT tubing, 3/4" dia, 2 terms/2 elbows/11 clamps per 100', to 15' high	L.F.	.91	.89			-2.20	5.16	-0.39
26 22 13.10 1500	Dry type XFMR, sgl ph, 240/480 volt pri, 120/240 volt sec, 25 kVA	Ea.	2,050	2,050				3,330	
26 24 16.30 0750	Panelboard, 3 ph 4 wire, main lugs, NQOD, 120/208 Volts, 100 A, 24 circuits	Ea.	775	775				1,757.50	
26 27 26.20 0200	Wiring device, toggle switch, quiet type, single pole, 15 amp	Ea.	5.30	5.30				19.38	
26 51 13.50 0600	Interior floor light fixture, acryl lens, 4-40 watt, 2'W x 4'L, clg mtd, incl lamps	Ea.	63	63				184.30	
26 71 13.20 0450	Motor, dripproof, 230/460 V, 1800 RPM, 1.15 service factor, 20 HP	Ea.	1,050	1,050				1,364	
Division 31 — EARTHWORK									
31 05 13.10 0700	Borrow, screened loam, load at pit, haul 2 mi round trip, spread w/200 HP dozer	C.Y.	25	26			4	34.79	3.27
31 05 16.10 0100	Borrow, bank gravel, load at pit, haul 2 mi round trip, spread w/200 HP dozer	C.Y.	26	21			-19.23	29.29	-15.81
0320	Borrow, crush stone, load at pit, haul 2 mi round trip, spread w/200 HP dozer	C.Y.	46.50	35			-24.73	44.69	-22.06
31 05 23.30 0020	Asphaltic concrete, plant mix, 145 Lb/CF	Ton	52	55			5.77	60.50	5.77
31 41 16.10 0900	Sheet piling, steel, no wales, 40' excavation, 38 PSF, left in place	Ton	1,025	1,025				1,478.50	
Division 33 — UTILITIES									
33 41 13.40 2140	Piping, storm drain, CMP, bitum ctd w/paved invert, 20'L, 24" dia, 14 ga	L.F.	29	27			-6.90	46.41	-4.53
60 2040	Piping, drainage & sewage, RCP, class 3, no gaskets, 24" dia	L.F.	27.50	24			-12.73	53.04	-6.77